KADUR DIVISION.

The 10th June 1896.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur division, up to 10th July 1896, for constructing a Taluk Cutcherry at Kadur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Taluk Cutcherry at Kadur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Description of work.	*Per.*	*Quantity.*
Excavating foundation	C.yds.	418
Filling foundation with stone in mortar	C.ft.	9,822
Basement do do	Do	3,238
Superstructure, burnt brick in mortar	Do	16,487
Arch work do do	Do	1,117
Stone slabs dressed finely for steps	S.ft.	369
Do for lintles	Do	119
Plastering with chunam	Sqr.	241·27
Color washing	Do	85·68
White washing	Do	170·82
Pointing with chunam	Do	9·75
Teakwood doors battened including frame with lock, &c., complete	S.ft.	569
Do do with iron work for Treasury	Do	23
Teakwood windows battened and glazed with iron bars 1″ (dia.)	Do	406
Teakwood ventilators with glazed shutters with iron bars ¾″ (dia.)	Do	70
Teakwood lower windows for side rooms	Do	14
Teakwood entrance gate with strong iron work, &c., complete	Do	57
Teakwood windows for prison with battened shutters and iron bars 1″ (dia.)	Do	96
Brick in chunam column	Lump sum in Rupees.	
Chocolate painting on doors and windows	Sqr.	25·00
Teakwood railing between Treasury and Sheristadar's seat	R. ft.	45
Teakwood work	C.ft.	473·06
Teakwood planking for lock-up rooms	S.ft.	636
Roofing with 1st class Mangalore tiles and teak reepers, complete, &c.	Sqr.	6,174
Ridging with do	R.ft.	336
Flat terrace to Treasury	Sqr.	1·15
Bengal terrace	Do	19·08
Flooring with flag stones	S.ft.	15·27
Flooring with concrete and plastering over it	C.ft.	1,372
Dental cornice work, ornamental, as per plan	R.ft.	174
Do plain	Do	876
Do above plinth of pillar	Do	250
Ornamental finials	No.	4
Wood oiling	Sqr.	40·00
Whiteant composition	Do	20·00
Bamboo outer rind matting	Do	23·67
Zinc gutters for valley of roof	R.ft.	50
Clearing site, filling pits and compensation for land, &c.	Lump sum in Rupees.	

D. RANGA RAO, *Offg. Executive Engineer.*